BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Schedule - B

NAME OF WORK: Providing water supply lines and other works in Chikkasandra and shettyhalli in W.No 12, Shettyhalli sub division

Sl.No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri D V Kumar	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2018-19, Page No.142, Item No. 19.1) including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 5 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per specifications and complete as per the direction of Engineer-in-charge of the work..	Cum	4265.78	211.0	Rupees Two Hundred Eleven Only
2	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete as per specifications and complete as per the direction of Engineer-in-charge of the work.	Rmt	5509.00	107.0	Rupees One Hundred Seven Only

D.V

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division.

Scanned by CamScanner

3	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour etc., complete as per specifications and complete as per the direction of Engineer-in-charge of the work.	Cum	4265.78	120.0	Rupees One Hundred Twenty Only
4	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials - Data rate approved by Chief Engineer, Dasarahalli zone etc., complete as per specifications and complete as per the direction of Engineer-in-charge of the work.	Sqm	220.00	1200.0	Rupees One Thousand Two Hundred Only
5	Providing and laying Pre Cast Drain Cover slabs of 250mm thickness including cost of all materials, labour, curing, transportation,loading, unloading etc etc., complete as per specifications and complete as per the direction of Engineer-in-charge of the work..	Sqm	30.00	3000.0	Rupees Three Thousand Only
6	Removing and resetting of foot path slab etc., complete as per specifications and complete as per the direction of Engineer-in-charge of the work.	Sqm	1368.00	208.0	Rupees Two Hundred Eight Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer.

Scanned by CamScanner